Grey Split Soap (Pencils) Firebrick

Division 04 masonry , Section 04 2100 clay facing brick

Highly porous, granular, and heavily textured finish, neutral medium gray.



Specification Data	
Division / Section	Division 04 masonry , Section 04 2100 clay facing brick
ASTM	C1261 Residential Fireplaces
Supplier	Metro Brick & Stone
Brick / Stone Type	Thin Brick
Typical Sizes	1-1/4" x 1-1/4" x 9"

Visual Characteristics	
Color Range	Grey
Texture	Sandy

Applications

-

Available Products

-

Images shown are for illustration purposes only. Actual product can vary.

Grey Split Soap (Pencils) Firebrick

Division 04 masonry , Section 04 2100 clay facing brick

Physical Properties

Verify project specific requirements before installation

Cleaning

https://prosoco.com/ Clean with masonry safe methods . Test all cleaning products on a small inconspicuous area

Installation (Standards / Codes)

Install in accordance with applicable masonry standards , local codes, and project specifications

Storage & Handling

Store dry, covered and elevated from grade Protect from jobsite contamination

Mortar Recommendations

Use mortar type and joint profile specified by the design professional. Mockups are recommend

Notes

1. **indentify the correct face side :** Ensure you distinguish between the face and the sawn back of the brick. The correct face will feature a fired clay surface typically displaying variegated colors, some with texture or paint. 2 ** achieve a uniform blend : ** Always draw brick from multiple sleeves simultaneously to achieve a well blended appearance. 3 ** Clean the bricks throughly : **. Wash each brick on both sides before installation. Although the bricks undergo rinsing after cutting , some dust may remain . 4. ** Plan ur layout ** Arrange the brick on the floor according to how you'd like the colors to blend on the wall . Instruct your installer to follow this pattern . 5 ** Utilize broken Brick ** Use any broken brick from the shipment for end cuts. Since used bricks may arrive with a few broken pieces, we include extras to ensure you have sufficient material